

Figure: 25 TAC §289.230(i)(11)(B)

Table I X-ray Tube Voltage in kV (kilovolt peak) and Minimum HVL		
Designed Operating Range (kV)	Measured Operating Voltage (kV)	Minimum HVL (millimeter of aluminum)
Below 50	20	0.20
Below 50	25	0.25
Below 50	30	0.30